No.	Items of work	Unit	Rate	Quantity	Rates to be tendered
			Rs. a. p.		Rs.
	IV. Waste Weir.				
	Constructing a masonry waste weir 140 ft. long at the right flank with Crest at R. L. 50.00 at the site of natural escape.				
1	Earthwork excavation for foundation ..	C.yd.	0 2 6	227	
2	Stone jelly concrete in surki mortar	,,	0 4 0	609	
3	Burnt size stone in surki mortar with bond stones	C.ft.	0 4 6	1,777	
4	Pointing with cement after scraping joints ..	Sqr.	3 8 0	5.62	
5	Burnt stone slab 6" thick dressed and fixed in mortar..	S.ft.	0 4 6	240	
6	Providing joggle joints	No.	0 8 0	20	
7	Rough stone work new with jelly backing ..	C.yd.	1 8 0	213	
8	Providing gravel ramp in front of weir ..	,,	0 6 0	31	
9	Cutting high ground in rear to apron level for free flow of water and unforeseen	L. S.	..	..	
	Total Rs. ..				

C. R. IYENGAR,
Executive Engineer.

HASSAN DIVISION.

Notification dated 24th March 1940.

Sealed tenders will be received at the Office of the Executive Engineer, Hassan Division, Hassan, up to 12th April 1940 till 3 P.M., for constructing Electrical Building at Saklespur.

2. Tenders in the prescribed form obtainable in the Office of the Executive Engineer, Hassan Division, Hassan, should be addressed to the Executive Engineer, Hassan Division, Hassan, and should be superscribed as "Tender for constructing Electrical Building at Saklespur. The name of the tenderer should also be superscribed on the sealed cover.

3. Each tender must be accompanied by a deposit of Rs. 620 only in cash as earnest money. The earnest money of the successful tenderer will be retained as cash security for the due fulfilment of the contract. (Cash amount will not carry any interest). In case of the acceptance of the tender an addition of the five per cent of the estimated amount as security deposit should be paid at the time of executing the agreement in the Public Works Department.

4. The tenders will be opened in the presence of such tenderers who wish to be present on the date of opening. The final acceptance of the tenders will rest with the Superintending Engineer, Shimoga Circle, who does not bind himself to accept the lowest or any tender, or to assign any reasons whatever for the rejection of any.

5. The name of the successful tenderer will be posted on the Notice Board in the Office of the Executive Engineer in due course. Within eight days of the acceptance of the tender, the successful tenderer will be required to execute the agreement in the departmental schedule contract form, for the due fulfilment of the contract.

6. Failure to comply with the condition 5 above or to agree to carry out the work in accordance with the specifications and agreements in force will entail forfeiture of the earnest money.

7. Copies of contract documents, estimates and drawings may be seen at any time at the Office of the Executive Engineer, Hassan Division, Hassan, on all working days between 11 A.M. and 5 P.M.

8. Specific rates should be given for each item in the schedule and the rates should be in rupees, annas and pies and expressed in words and figures.

9. Any rates or lumpsum amounts for the items not called for, if tendered by the tenderer, will not be taken notice of. The rates tendered should include all such lumpsum items.

10. No alterations which are made by the tenderers in the contract documents in the nomenclature of the sanctioned sub-heads will be recognised and if corrections are made, the tenders will be liable to rejection.

11. There should be no corrections or erasures in the tenders in the rates of items and any corrections made in the rates should be attested to and the number of corrections, if any, in each page noted at the foot of the same by the tenderer.

12. No reference should be made to the P. W. D. Current Schedule of Rates.

13. On the event of the tender being submitted by a firm, it must be signed separately and severally by each member thereof or in the event of absence of any partner, it must be signed on his behalf by a person holding power-of-attorney authorising him to do so.

14. When once the rates tendered have been accepted, they will not be revised under any circumstances. In regard to items of work not tendered, the rates to be proposed by the Executive Engineer, Hassan Division, Hassan, and approved by the Superintending Engineer shall be final and legally binding on the tenderer.

15. The quantities as estimated are only approximate and are liable to alterations, omissions, deductions or additions, at the discretion of the Executive Engineer or his representative. The tendered rates will hold good for any quantity whether higher or lower than those estimated for.

16. The work should be completed as per departmental specifications for different items and handed over to the P. W. D. by the end of June 1940, failing which the Executive Engineer may, at his discretion, levy a penalty up to Rs. 500 which will be recovered from the contractor's outstandings for the period exceeded by him till the work is completed and handed over.

17. In all matters of dispute of any kind, not specially provided for in the agreement or of rates, penalties, measurements, quantity of work, etc., the decision of the Executive Engineer shall be final and legally binding.

18. The earnest money of rejected tenders will be returned on surrender of the receipts originally granted, along with an application to the Executive Engineer, Hassan Division, Hassan.

19. No claims for damages for delays caused by officers of the department in the execution of work will be considered, whatever may be the reason for such delays. Contractors should bear this in mind when tendering for work. Extension of time due to delays caused by the Departmental Officers will however, be considered on the merits of each case.

20. The contract should not be sublet.

21. All materials, tools, plant and machinery that will be supplied by the department in the interest of the work shall be accepted by the tenderer at the rates fixed by the Executive Engineer and the tenderer will pay the hire, etc., on machinery at the prescribed per cent per annum of the booked value of the tools and plant supplied from the date of taking over of tools and plant from the Stores to the date of return to the Stores, the dates considered being the dates of acknowledgments of the vouchers in each transaction.

22. The contractors should arrange for the payment of royalty and tolls.

23. **Copies of tender in the prescribed form are available from the Office of the Executive Engineer only on a payment of Re. 0-4-0 per form.**

Abstract quantities for constructing Electrical Buildings at Saklespur Town, Hassan District.

Sl. No.	Items of work	Per	Rate	Quantity
	I. *Abstract quantities for constructing one block of Linemen's Quarters for four Coolies.*		Rs. a. p.	
1	Earthwork excavation for foundation and filling in basement ..	C.yds.	0 3 0	29
2	Stone jelly concrete in lime mortar 1 : 2 for foundation ..	C.ft.	0 4 0	309
3	Size stone in clay for foundation and basement including bond stones at 6 feet apart	„	0 3 6	741
4	Burnt brick in lime mortar	„	0 5 0	510
5	Stone slabs 4" thick roughly dressed and fixed in mortar ..	S.ft.	0 5 6	129
6	Stone slabs 6" thick exposed parts one line dressed and fixed in mortar	„	0 9 0	21
7	Chunam plastering 2 coats	Sqrs.	3 8 0	43·14
8	Cement pointing with thread lining	„	3 8 0	2·07
9	White and colour washing 2 coats	„	0 4 0	44·64
10	Roofing with first class Mangalore tiles on T. W. reepers 2"×1" including wood-oiling and tieing the tiles to double reepers with galvanized wire	„	26 0 0	15·34
11	Providing and fixing Ridge tiles set in mortar and cement pointing complete	R.ft.	0 8 0	78
12	Providing and fixing ventilating tiles big size fixing, etc., complete	No.	2 8 0	16
13	Teak wood wrought and put up including 2 coats of wood oiling	C.ft.	5 0 0	65·13
14	Teak wood doors battened 1" thick shutters with all iron fixtures complete (frames 3"×4") and flat iron clamps 1' long and 2" wide	S.ft.	1 8 0	156
15	Teakwood battened windows 1" thick shutters and $\frac{5}{8}$" diameter iron bars with all iron fixtures, etc., complete	„	1 14 0	75
16	Teakwood shelves with frames, shutters and self planks, etc., complete	S.ft.	1 8 0	60
17	Chocolate painting 2 coats doors both sides	Sqrs.	3 8 0	7·52
18	Constructing sinks in bath rooms complete	No.	10 0 0	4
19	Providing stone mortar and pestle fixed complete	„	5 0 0	4

Sl. No.	Items of work	Per	Rate	Quantity
			Rs. a. p.	
20	Flooring with 3″ lime concrete (1 : 3) and 1½″ cement concrete (1 : 2 : 4) on top with ½″ cement plastering (1 : 3) on top complete with red ochre colour	Sqrs.	20 0 0	5·50
21	Do do without red ochre colour ..	,,	18 0 0	2·50
22	Levelling ground, etc.	L. S.	..	100
23	Providing and fixing 'teakwood' planks with Teak wood pegs, complete	S.ft.	0 9 0	100
24	Constructing "U" shaped drain 4″ in lime concrete as per specification	R.ft.	0 6 0	70
25	Chunam patty brick in lime mortar 3″×6″ plastering, etc., complete	,,	0 2 0	125
26	Excavating soakage pits 5′×5′×6′ and filled with brickbats of 1½″ to 2″ size well burnt and covered with 1″ thick red earth and connecting the drain to it with a galvanised pipe 3 to 4″ dia. and an iron grating at an entrance, etc., complete	L. S.	..	10
27	Burnt brick in clay for superstructure	C.ft.	0 3 6	1,533
	II. *Abstract quantities for constructing one unit of double block of Operators' Quarters.*			
1	Earthwork excavation foundation and filling in foundation ..	C.yds.	0 3 0	53
2	Stone jelly concrete in mortar	C.ft.	0 4 0	597
3	Size stone in clay foundation and basement with bond slabs at 6′ apart	,,	0 3 6	1,079
4	Burnt brick in clay for superstructure with necessary bond slabs	,,	0 3 6	1,946
5	Burnt brick in lime mortar superstructure as per deduction ..	,,	0 5 0	746
6	Supplying and fixing burnt stone slabs 6″ thick dressed and fixed.	S.ft.	0 8 0	249
7	Cement pointing to basement all round with thread lines ..	Sqrs.	3 8 0	2·20
8	Chunam plastering 2 coats	,,	3 8 0	50·00
9	White and colour washing 2 coats as per plastering and pointing	,,	0 4 0	52.20
10	Plain cornice 9″ thick as per design	R.ft.	0 12 0	63
11	Burnt brick in lime parapet wall 9″ thick as per design ..	,,	1 0 0	60
12	Flooring with 1½″ thick cement concrete over 3″ lime concrete with ½″ cement plaster on top complete coloured red and cut to tile pattern	Sqrs.	18 0 0	9·00
13	Roofing with first class Mangalore tiles on teakwood reepers 2″×1″ including wood oiling to reepers	,,	26 0 0	12·28
14	Ridge tiles set in mortar and cement pointing	R.ft.	0 8 0	78
15	Madras terrace complete with 3″ surki concrete 2 course of flat tiles surface and ceiling plastered with necessary sloping to drain of water	Sqrs.	35 0 0	3·74
16	Plain teakwood eaveboards 9″×¾″ fixed, etc. complete ..	R.ft.	0 8 0	149
17	Teakwood wrought and put up complete with wood oiling 2 coats	C.ft.	5 0 0	85·51
18	Doors with teakwood frames of 3″×4″ and honney wood battened shutters 1″ thick with iron fixtures and, etc., complete	S.ft.	1 8 0	280
19	Teakwood windows with 3″×4″ frames with honney wood battened shutters and ⅝″ thick iron bars with iron fixtures, etc., complete	S.ft.	1 8 0	116
20	Teakwood cup boards with panelled shutters locking arrangements and teak wood planks for shelves, etc., complete ..	S.ft.	1 4 0	96
21	Rolled steel girders complete including painting 2 coats (Tata's tested)	Cwt.	15 0 0	6·36
22	Expanded metal 3″×1½″ mesh with ⅛″ strands. Teakwood frame work with doorways, etc., complete	S.ft.	0 10 0	123
23	Chocolate painting two coats for doors and windows ..	Sqrs.	3 8 0	13·33
24	Providing and fixing ventilating tiles, big	Each	2 8 0	8
25	Constructing sinks complete with outlet pipes	Each	10 0 0	2
26	Providing and fixing stone mortar and pestle	,,	5 0 0	2
27	Chunam borders at ends of roof	R.ft.	0 2 0	24
28	Rainwater down pipes of 3″ dia. of plain G. I. sheet fixed with clamps, etc., complete including painting	R.ft.	0 6 0	65

Sl. No.	Items of work	Per	Rate	Quanti y
			Rs. a. p.	
29	Providing and fixing brass or copper handles in bath room ..	Each	1 8 0	2
30	Constructing chimney etc., in kitchen	„	10 0 0	2
31	Levelling ground	L. S.	..	100
	III. *Abstract quantities for constructing Combined Station Office and Stores Building.*			
1	Earthwork excavation and filling in basement	C.yds.	0 3 0	39
2	Stone jelly concrete in lime mortar for foundation	C.ft.	0 4 0	361
3	Size stone in lime mortar foundation and basement with bond stones at 6 feet apart in every course	„	0 5 0	869
4	Burnt brick in clay with necessary bond slabs	„	0 3 6	1,298
5	Brick in mortar superstructure	„	0 5 0	144
6	Stone slabs 6″ thick roughly dressed and set in mortar ..	S.ft.	0 8 0	177
7	Stone slabs 3″ thick exposed parts 1 line dressed and set in mortar	„	0 5 6	7
8	Brick in mortar pillars 1½′ square and 9′–9″ high including stone base and capital and cement plastering ½″ thick, etc., complete	Each	10 0 0	4
9	Chunam plastering 2 coats	Sqrs.	3 8 0	29·00
10	Cement pointing with thread lines	„	3 8 0	1·88
11	White and colour washing two coats as per plastering and pointing	„	0 4 0	31
12	Burnt brick in mortar cornice as per design	R.ft.	0 12 0	158
13	Brick in mortar parapet wall 9″ thick as per design	„	1 0 0	155
14	Chunam moulding 6″×½″ all round ventilators	„	0 1 0	77
15	Chunam moulding in front of wall between pillars	No.	10 0 0	3
16	Flooring with 1½″ cement concrete on 4″ thick stone jelly concrete bed in lime mortar and plastering the top with ½″ thick cement smooth plastering and coloured red in tiled patren	Sqrs.	20 0 0	6·00
17	Madras terrace with 3″ surki concrete and 2 course of flat tiles surface and ceiling line plastered, etc., complete ..	„	35 0 0	7·50
18	Steel work fixed complete with 2 coats of painting	Cwt.	15 0 0	10
19	Teakwood door panelled 1½″ thick shutters with iron fixtures and 3″×4″ frames, etc., complete	S.ft.	1 8 0	92
20	Teakwood windows with glazed shutters 1″ thick with ⅝″ dia. with iron fixtures and 3″×4″ frames, etc., complete, shutters to be in 4 leaves	S.ft.	2 0 0	70
21	Teakwood ventilators fully glazed with iron bars	„	1 6 0	27
22	Chocolate painting two coats	Sqrs.	3 8 0	12·87
23	Fixing wire gauge shutters with teak wood reepers complete ..	S.ft.	0 8 0	63
24	Cast iron down take pipes with heads and bends 3″ diameter embedded in masonry	R.ft.	1 6 0	78
25	Brick in lime mortar and stone slabs with chunam plastering, etc., complete for brackets	L. S.	..	10
26	Clearing site and levelling ground, etc.	„	..	100
27	Teakwood work wrought and put up including wood-oiling, etc., complete	C.ft.	5 0 0	62
	IV. *Quantities for constructing one unit of Latrine.*			
1	Earthwork excavation for foundation	C.yds.	0 3 0	4
2	Size stone in clay foundation and basement	C.ft.	0 3 6	130
3	Burnt brick in mortar superstructure	„	0 5 0	196
4	Chunam plastering	Sqrs.	3 8 0	4·91
5	Cement pointing with thread line	„	3 8 0	0·56
6	White and colour washing, two coats	„	0 4 0	5·47
7	Cement plastering ½″ thick all round interior	„	8 0 0	0·79
8	Tar washing 2 coats	„	1 8 0	0·63
9	Flooring with 3″ concrete and 1″ cement concrete and ½″ cement plastering, etc., complete	Sqrs.	16 0 0	0·38
10	Fixing outlets and constructing drain	L. S.	..	10
11	Providing galvanised iron sheet tubs 12″×6″ complete with tarring	Each	0 8 0	6

N.B.—Five such latrines have to be constructed.

P. SUBBA RAO,
Executive Engineer.